BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of work :Providing Chain link Fencing in Sanjeevininagar and Gundajanaya Temple opp Govt Land in ward No.7 Kodigehalli sub division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	33.75	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1 (a) /2.3.5 (Page No. 5 & Item No. 2.3)	Cum	**172.78**	
2	4.50	KSRRB 2900-4.1: Providing and laying in position plain **cement concrete mix 1:4:8** with stone aggregate 40mm and down size in foundation upto a depth of 2m below ground level and upto a height of 1.5m above ground level / bed level machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, cost of all materials, labour, HOM of machineries, curing complete as per specifications. **(Page.12 & Item No. 4.3)**	Cum	**4757.28**	
3	4.50	KSRB 4-1.5 : Providing and laying in position **plain cement concrete** of mix **1:2:4** using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per	Cum	**5228.98**	
4	108.00	Supplying and fixing **M. S. Rectangular Poles** made but of 2 equal angles of 65 x 65 x 6 mm welded together and fixed inCC (1:2:4) with 2 Nos. 16 mm dia M. S. hold fast rods each of length 25 cms, including cost of all materials, cutting, bending scafolding wherever	Cum	**1093.92**	
5	1000.00	Providing and fixing **M. S. Block Pipe** of 38 mm dia, of heavy guage of 1:4, including removing the bends, cutting the pipe in between the two verticle poles (M. S. Rectangular Poles) and spot welding the chain link with M. S. Block Pipe, including cost of all materials, wastage in cutting and scaffolding wherever necessary, with all lead and lift as directed by the Engineer-in-charge of the work etc., complete including 2 coats of approved quality paint over one coat of shop painting (Page No. 231 & Item No. 37.4 PWD SR 2014-15	Rmtr	**316.94**	
6	750.00	Providing **Chain Link Fencing** 50 mm size of 8 guage property striched between rectangular poles and fixed with suitable bolts and nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required, including cost of all materials, labour, lead and lifts, cutting, bending scafolding wherever necessary, wastage and lapping etc., complete as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (Page No. 231 & Item	Sqm	**669.92**	

ಕಾ.ಅ. (ಬೊ.ವ.)

7	33.75	Lead for disposal of debris shall be payable at Carriage rates by mechanical means with all lead and lift, loading, undloading and labour charges etc.,complete and as per the directions of the Engineer-in-charge of the work.	Cum	**67.32**	

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....NIL
ತಿದ್ದುವಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore-92